BRUHAT BANGALORE MAHANAGARA PALIKE

Comparative Statement

Sculpting & Erecting proposed NADAPRABHU KEMPEGOWDA Statue

Ref:-BBMP/YNK/EE (Project)/QTN/07/2019-20 Dt:20-11-2019

Sl. No.	Description of Work	Unit	Qty.	Sri Abhayanjaneya Swamy Hoysala Shilpa Kala Mandira		Sri Bataganganma Shilpakala		Sri Basaveshwara Hoysala Shilpa Kala Mandira	
				Rate/ Unit	Amount	Rate/ Unit	Amount	Rate/ Unit	Amount
1	NADAPRABHU KEMPEGOWDA (STANDING) bronze sculpture with following specification a) Making of clay modeling as per the approved schematic sketch b) Making of POP negative mould as per the approved clay model c) Making of FRP (Fiber Reinforced Plastic) casting master pattern d) Making of Bronze Metal (88% of copper and 12% of tin) casting by ABC mould by silica sand process with all necessary melting process materials e) Making of hand carving/ Chiseling grinding, brazing, antic bronze oxidizing by acid process including cost of bronze ornamental finishing f) Imported PU Poly utherin lacqor coating g) The height of the Statue would be about 10 feet height supported on 01 feet height pedestal with a weight of about 1200.00 kgs (apporx) excluding weight of MS supporting fabrication work for strengthening of statue including cost of all necessary raw materials, labour, artizans and semi artizans works including erection, with all applicable taxes etc., (Including Erection and transportation charges etc.,) complete as per the direction of engineer in charge.	Job	1	4700000.00	4700000.00	5000000.00	5000000.00	5100000.00	5100000.00
2	EQUESTRIAN (MOUNTED ON HORSE) NADAPRABHU KEMPEGOWDA Statue of bronze sculpture with following specification a) Making of clay modeling as per the approved schematic sketch b) Making of POP negative mould as per the approved clay model c) Making of FRP (Fiber Reinforced Plastic) casting master pattern d) Making of Bronze Metal (88% of copper and 12% of tin) casting by ABC mould by silica sand process with all necessary melting process materials e) Making of hand carving/ Chiseling grinding, brazing, antic bronze oxidizing by acid process including cost of bronze ornamental finishing f) Imported PU Poly utherin lacqor coating g) The height of the Statue would be about 18 feet height, 20 feet length and 6 feet wide supported on 02 feet height pedestal with a weight of about 4850.00 kgs (apporx) excluding weight of MS supporting fabrication work for strengthening of statue including cost of all necessary raw materials, labour, artizans and semi artizans works including erection, with all applicable taxes etc., complete as per the direction of engineer in charge.	Job	1	19400000.00	19400000.00	19700000.00	19700000.00	20100000.00	20100000.00

Scanned by TapScanner

	Description of Work	Unit	Qty.	Sri Abhayanjaneya Swamy Hoysala Shilpa Kala Mandira		Sri Bataganganma Shilpakala		Sri Basaveshwara Hoysala Shilpa Kala Mandira	
				Rate/ Unit	Amount	Rate/ Unit	Amount	Rate/ Unit	Amount
3	Transportation of above statue to the work spot and fixing with necessary fixtures on a platform of about 40"feet height (apporx) including hire charges of all machineries loading & un loading charges, Transportation, Scaffolding, Bracing, Erection & Finishing with necessary labour, applicable taxes etc., complete as per the direction of engineer in charge.	Job	1	560000.00	560000.00	590000.00	590000.00	620000.00	620000.00
					L1		L2		L3

As seen from the above statement the item wise rates quoted by **Sri Abhayanjaneya Swamy Hoysala Shilpa Kala Mandira,** is the 1st lowest rate which is least compared to others. Hence recommended for kind approval.

The above rates are inclusive of with all aplicable taxes

The above rates are only for Estimate Preparation.

"DATA RATE APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.

Executive Engineer 20/11/13
Project Division,Yelahanka
Bruhat Bangalore Mahanagara Palike

Scanned by TapScanner